
ENERGY EFFICIENCY


Measure File Guide HVAC - Chiller

January 2025






IA Phase – Measure File



- Site Information: Includes the Site Name, Line Item, Cooling Equipment # (useful in labeling inspection photos), Room location/floor, and Building Type. If unsure about the Building Type, contact the Project Manager.
- 2. Cooling Equipment Type: Select the HVAC equipment technology being installed.
- 3. Model and Serial # (Pre): Must be provided for all units being removed.

Pre Retrofit Equipment Information





Post Equipment Information

- Model and Serial # (Post): Must match inspection photos and AHRI certificate/simulation for installed equipment.
- 5. Cooling Capacity Type: Net total cooling capacity in tons.
- 6. Installed Efficiency: Should reference the manufacturer simulation at AHRI conditions.

± ± ± ± ± ± 0.5589 0.3262 0	Full Load (kW/Ton)	Efficiency (in Part Load (kW/Ton)	Heating (kW/Ton)	Building Description	Primary Business Activity	Operat Hours	HVAC Operat Hours	Combi HP for Conde Water Pumps & CT Fans
0.5589 0.3262 0	Ŧ	Ŧ	Ŧ	Ŧ	Ŧ	Ŧ	Ŧ	Ŧ
	0.5589	0.3262	0					





FA Phase – Pre-Inspection

The following is required:

- 1. Photo of Name Plate and Profile: Please label each picture with the Measure Item from the Measure File. Compile all photos into a single PDF document to upload to EEPM for Pre-Inspection Desk Review.
 - If units are considered Early Retirement (ER), include a photo of the load display and/or set point to demonstrate operability.
- 2. Equipment specification sheet: Used to verify equipment characteristics.
- **3. Supporting Documentation:** For units 20 ton or below, attach AHRI certificate. For units above 20 tons, include manufacturer specifications showing unit performance at AHRI conditions.

IN Phase – Post-Inspection

The following is required:

- 1. Photo of Nameplate and Profile: Please label each pictures with the Measure Item from the Measure File. Nameplate must have model and serial number. Include a photo of the room or area showing the equipment quantities and operability. This can be demonstrated by including a photo of the display and/or set point. Compile all photos into a single PDF document to upload to EEPM for Pre-Inspection Desk Review.
- 2. Installation Notice Certificate: Generated by EEPM, signed by Customer and Service Provider, including an installation completion date.
- **3. Project Invoice:** Includes Customer name, project address, model number and quantity that matches the Measure File, labor materials and other cost associated with installation.

Simulation Requirements

Water Cooled Chillers:

- Condenser Water Entering Temp 85 deg F and Flow Rate 3.0 gpm/ton
- Evaporator Leaving Temp 44 deg F and Flow Rate 2.4 gpm/ton

Air Cooled Chillers:

- Entering Air (ambient air temp) Dry Bulb Temp 95 deg F
- Evaporator Leaving Temp 44 deg F and Flow Rate 2.4 gpm/ton

90.1 OMPLIANT	Intertek UL STD 199 3110178 CERTIFIED
035-18188-000 REV A	CAN/CSA STD C22.2 NO.2
THE WAARD-CARVARDAVENCIAL ARE RECEIPTING	waaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaaa
An I prese Pressure Sad Cit. Her 23 22	at Handland Salth Lander (1220)
COOR USE Vice Plant United United States	Argunal Parts 1010 Descent Table Descent 841 834 834 8314 934 834 834 834
Australian David Artige Nam David Man David Man David Statistic Angelitik Statistic Statistic	
SVORK MAIN	

